

ADDENDUM NO. 1

**BID NO. 26-04
SOUTH DRIVE SEWER INTERCEPTOR**

To all holders of the specifications, the following corrections are hereby made. All other items shall remain unchanged. This addendum shall become part of the Contract Documents for the above referenced project.

Acknowledgement of Addendum

Name: _____

Company: _____

Date: _____

Signature: _____

The following items were discussed at today's Pre-Bid meeting:

Q1: Can you verify the linear feet of 12" PVC pipe required?

A1: The amount of 12" PVC is confirmed to be 1450 LF. (18" is 150 LF)

Q2: Can you define the staging area?

A2: The grass islands in the middle, and the cul-de-sac at the end, of South Drive are available for staging and vehicle parking.

Q3: What should be done with the trees in the grass island over SP-0044?

A3: The City prefers that the trees remain in place, but if the contractor determines that these trees absolutely need to be removed, the City will have the trees removed.

Q4: Can a flow rate be provided for the purposes of specifying a bypass on the 18"?

A4: The information has been requested from City operations staff and will be provided as soon as possible by way of an additional addendum.

Q5: What liner is specified for the new pre-cast manholes?

A5: New pre-cast manholes are required to have Dura-Plate (or equivalent) lining.

Q6: What backfill materials are allowed?

A6: Excavated spoils are to be hauled off. The contractor shall backfill excavated areas with properly compacted CR-6 (or CR-8) only.

Q7: Is any curb, sidewalk, or any other concrete included in the project scope?

A7: Any concrete that is removed or damaged as part of contractor's activities shall be incidental and shall be replaced in kind within the scope of the project.