

October 16, 2024

ADDENDUM NO. 5

BID NO. 25-04

**SEWER REHABILITATION
ANNUAL CONTRACT**

To all holders of the specifications, the following corrections are hereby made. All other items shall remain unchanged. This addendum shall become part of the Contract Documents for the above referenced project.

Acknowledgement of Addendum

Name: _____

Company: _____

Date: _____

Signature: _____

Q1: Is the bond amount to be provided for the total of the bid schedule line items or will each work order have to be bonded individually?

A1: Please refer to Addendum No. 3 – The entirety of the contract scope for each annual period will be released at the start of each contract term. The bond shall be provided for the total of the amount of work released at that time.

Q2: Will the 10% retention be held for the full annual life cycle of the contract or on a work order basis?

A2: Given that the entirety of the scope will be released at once, the 10% retention will be held for the full annual life cycle of the contract.

Q3: Will completion schedules be given on a work order basis and liquidated damages assessed per work order?

A3: Completion schedules, deadlines and damages will be based on the entirety of the scope of work released at one time at the beginning of each contract year.

ADDENDUM NO. 5 BID NO. 25-04 (cont.)

Q4: Could you please provide guidance on how we can access information regarding wage scale?

A4: This project does not include provisions for scale, prevailing wages, etc.

Q5: Regarding the installer experience requirements for this project, please let me know if we would be an eligible installer [based on experience outside of Aberdeen,etc],

A5: Please refer to Addendum No. 2. Please provide a synopsis of the experience you have as it is applicable to the scope of this project or as it is comparable in scale to Aberdeen's Collection System. All proposals will be considered and compared based on the quality of information presented.

Q6: What is the desired length of lateral launching required? Per addendum 3, the lateral liner is to extend 6' is this the maximum or are farther lengths possible?

A6: The minimum lateral liner (from the main only) is six (6) feet. Longer lengths may be requested if feasible after CCTV pre inspections.

Q7: Will cleanouts be present for longer liners or laterals with transitions?

A7: Lateral linings of this nature will most likely only be requested if there is a cleanout present and conditions are proven favorable in CCTV pre inspections.

Q8: Please confirm contractor is allowed to release filtered water removed during the pipe vacuuming process back into the sanitary system. If yes, please confirm that you have been authorized by the sanitary sewer operator to grant this permission.

A8: Yes authority is provided by the wastewater operator to grant contractor release of filtered water removed during the pipe vacuuming process back into the sanitary system. Contractor shall provide specs of system used along with other project submittals for approval after award.

Q9: Are there any well water areas, wetland areas, ground water or other sensitive environments proximate to the work area? If so, are there specific controls required to protect these areas such as "pre-liners"?"

A9: There are wellhead protection areas located throughout the City, no specific controls as mentioned are required in the scope of this contract.