

ADDENDUM NO. 4**BID NO. 25-08****SR-2 CARSINS RUN TRIBUTARY RESTORATION
CITY OF ABERDEEN, MARYLAND**

To all holders of the specifications, the following corrections are hereby made. All other items shall remain unchanged. This addendum shall become part of the Contract Documents for the above referenced project.

Acknowledgement of Addendum

Name: _____

Company: _____

Date: _____

Signature: _____

THE FOLLOWING TOPICS WERE DISCUSSED AT THE PRE-BID MEETING 11-22-24:

-Assume trees are all salvaged through clearing and grubbing operations.

-Microtopography can it be scarified with excavator bucket, does not have to be 'disked or chisel plowed'

-KCI is preparing a SWPPP and will submit the NOI. Responsibility will be transferred to the Contractor.

-For bidding purposes, assume fill material is salvaged from the large 'fill hill' on the Summerlin property at the site. Contractor will have to stabilize disturbed area following disturbance.

-Raw fill volume is 1188 CY (no adjustment) and is reduced by the subgrade material that will offset this volume (bed mix, woody toe, toe boulder, log sills...) to determine the adjusted volume of 813 cy. The sand and gravel for the washing of the riffles is incidental to the riffles.

-All work shall be completed no later than August 31, 2025, with the exception of the live stake planting, which will occur during the dormant season (fall or winter 2025).

-Instruction to bidders Article 19.02 Evaluation of Bids

A. Omit the last sentence.

B. The evaluation weighting factor is revised per the table below.

<u>Weighting Factor</u>	<u>Criterion</u>
60%	Price
30%	Qualifications/Experience with Similar Projects
10%	Project Schedule