

ADDENDUM NO. 3

BID NO. 19-01

STREET RESURFACING AND REPAIR, CITY OF ABERDEEN, MARYLAND

To all holders of the specifications, the following corrections are hereby made. All other items shall remain unchanged.

The following are answers to questions posed by bidders:

Q1: What is the budgeted amount to be spent for FY19?

A1: The budget amount for the FY19 Street Resurfacing project is \$1,000,000.

Q2: Why aren't the quantities on the manholes and water vales per street listed on the bid form?
It the bid supposed be incidental work requirements?

A2: The cost of any manhole and valve adjustments should be incidental to the paving.

Q3: Are liquidating damages capped at \$300 per day as per Section 4.1 of the General Provisions?

A3: Liquidating damages are capped at \$300 per day for any contract price over \$500,000.

Q4: The specifications call for 1.5" surface depth, as stated in section 4.3.1. of the Special Provisions. The bid form lists 2" surface depth. Is 2" the correct depth?

A4: The 2" depth is the correct depth.

Q5: Why is the last sentence included in Section 4.2.1. of the Special Provisions?

Section 4.2.1. of the Special Provisions states:

"...This item does not apply to milling operations necessary to complete Item 501 or 503."

A5: The following sentence shall be **removed** from section 4.2.1. of the Special Provisions:

"This item does not apply to milling operations necessary to complete Item 501 or 503."

Q6: Section 4.1.1.2 of the Special Provisions states that the contractor will get paid up to 5% increase on required asphalt, but is the increase 5% or 15%?

A6: Section 4.1.1.2 of the Special Provisions allows for an adjustment in unit price for hot mix asphalt to account for an increase in asphalt binder if the asphalt binder cost fluctuates above 15% since this contract is for one year and the estimated mix quantity is less than 10,000 tons.

Q7: For the CR6 Stone specified in the bid form, will the contractor get paid for 1000 tons of stone or is this line item considered incidental work?

A7: The undercut and refill will be considered incidental to the unit cost of the CR6 item.

Q8: Should driveways be included as a separate item on the bid form? In case driveways or sidewalks need to be replaced?

A8: Any transition required between the back of the curb and existing sidewalk or driveway will use the concrete sidewalk line item listed on the bid form.

Q9: Is there a list of street names?

A9: The list of street names and pictures are attached to this Addendum as Appendix No. 2

Bid Form

Q10: Adjustment of existing utilities: if the project is milling and replacing 2" of HMA, theoretically the grade does not change, therefore do we assume that all utilities that are acceptable (and functioning properly in the case of the drainage inlets) prior to construction activities, and are not damaged by construction activities, will not be adjusted?

A10: It is an acceptable assumption that all utilities will not need to be adjusted for milling.

Q11: What is the criteria for price increases (in addition to asphalt cement) for option years 2 and 3? There are many costs other than the asphalt cement (e.g. :labor, fuel, equipment and subcontractors) that could increase substantially during a 3 year period.

A11: There are no other price adjustments proposed.

Q12: What does it mean in Special Provision Section 1.1.4. "Incident to the contract, milling wider than two feet (2') shall be at the expense of the contractor"?

A12: The following sentence shall be **removed** from the Special Provision Section 1.1.4. "Incident to the contract, milling wider than two feet (2') shall be at the expense of the contractor."

Q13: What is item 505 CR-6 stone base used for?

A13: This item will be used as needed to provide fill under and in front of any replacement curb and under any replacement sidewalk.

Q14: Is the project milling "taper" mill for transitions along the curbs and at the project limits or is the milling "full mill" over the entire roadway, edge to edge?

A14: The milling is intended to be full width milling of roads prior to resurfacing.

Q15: Do you have a record available of the quantities paid to the contractor (not prices necessarily) on this contract in prior years?

A15: Attached as Appendix No. 1 is a worksheet of the quantities from last fiscal year. This was a \$500,000 contract year.

Q16: What is item 501A – 2" Bituminous base used for?

A16: For the front of curb replacement or in areas where the City of Aberdeen wants to thicken sections of the road beyond the 2" surface layer.

Bid Form

Appendix No. 1

FY 2018 Street Resurfacing Quantities

Item No. 501 Surface – Amount Used: 7444.46 Ton

Item No. 501 B Base – Amount Used: 0 Ton

Item No. 502 Wedge – Amount Used: 369 Ton

Item No. 503 Repair – Amount Used: 191 Ton

Item No. 504 Milling – Amount Used: 79,854 SY

Item No. 505 CR6 – Amount Used: 120 Ton

Appendix No. 2
2019 Paving Priorities

Priorities	Street Name	Location	Scope of Work			
1	Chestnut Street	Elm St. to Third St.	Curb Replacement & Road Reconstruction			
2	Oak Street	Chestnut St to Elm St	Curb Replacement & Road Reconstruction			
2	Old Philadelphia Road	Rte 40 to Perryman Road	Mill & Overlay			
3	Post Road	MD 22 to E. Bel Air Ave.	Mill & Overlay			
4	Steven's Alley	Post Road to New County Road	Mill & Overlay			
5	Raymond Ave	APG Rd to Post Road	Curb Replacement, Mill & Overlay			
6	Poplar Alley	Warren St. to Plater St.	Mill & Overlay			
7	Norman Ave	APG Rd to Post Road	Mill & Overlay			
8	Chesapeake Court	Victory St	Mill & Overlay			
9	Chapel Alley	Walnut Street to Franklin Street	Mill & Overlay			
10	Howard Street	W. Bel Air Ave to Franklin St	Mill & Overlay			
11	Alley C	Brentwood Area (Near Custis St)	Mill & Overlay			
12	Carter Street	Bonnett Street to Wyn Mar Ave	Mill & Overlay			
13	Cooke Street	Bonnett St. to Wyn Mar Ave.	Mill & Overlay			
14	WynMar	Edmund to Cooke	Mill & Overlay			
15	Crestmont Drive	Hemlock Lane to End	Mill & Overlay			
16	Hillman Court	Crestmont Dr. to End	Mill & Overlay			
17	Pleasantwind Drive	Windemere Dr. to Beards Hill Rd.	Mill & Overlay			
18	Rabbit Run Alley	Laurel Lane to Mt. Royal Ave.	Mill & Overlay			
19	South Drive	Edmund Street to End	Mill & Overlay			
20	Brannan Alley	Osborne Rd to Brannan Rd	Mill & Overlay			



Chestnut Street at Elm Street



Chestnut Street at Elm Street



Old Philadelphia Road at MD 715 Looking West



Post Road at MD 22 Looking West



Raymond Avenue at Post Road Looking North



Poplar Alley at Plater Street Looking South



Poplar Alley at Market Street Looking South



Norman Avenue at Post Road Looking North



Chesapeake Court at Victory Street Looking North



Chapel Alley at Robinson Avenue Looking North