



May 3, 2021

CITY OF ABERDEEN
Department of Public Works
Utility Roadwork Restoration Requirements
Policy and Procedures

Purpose

The City's Department of Public Works requires all utility providers and their contractors (Electrical, Gas, Communication, etc.) to fully restore a City-owned roadway due to new utility installation or repairs which affecting the integrity of the pavement, curb, gutter, sidewalk, or any other public feature in the Rights of Way. This policy and procedure, effective the date of this notice, requires all utility providers or their contractors to comply with this policy.

General Procedures

1. Roadway repairs are to follow the Harford County Plate R-4 for road repair: 1' cut back and 9" deep. (See Attached)
2. Roadway repairs that occur on roads that have been paved within 5 years, must be milled, and overlaid after repair curb to curb and to the complete satisfaction of the Permit Inspector and the City Engineer.
3. Road work that occurs only on one side of the roadway and on roadways that have not been paved within 5 years must be milled 1.5 inches and overlaid with 9.5 mm or 12.5 mm surface asphalt roadway from curb to centerline and to the complete satisfaction of the Permit Inspector and the City Engineer. This includes all mains/service utility repairs or replacements.
4. Road work that occurs on both sides of the roadway and on roadways that have not been paved within 5 years must be milled 1.5 inches and overlaid with 9.5 mm or 12.5 mm surface asphalt the entire roadway from curb to curb and to the complete satisfaction of the Permit Inspector and the City Engineer. This includes all mains/service utility repairs or replacements.
5. All line striping is to be repainted (when applicable).
6. Green areas and concrete areas affected by any utility repair work shall be restored to its original condition to the complete satisfaction of the Permit Inspector and the City Engineer.

For further questions, please contact the City Engineer, Ms. Rolla Chng at 410-272-1600 x 222 or City Inspector, Mr. Brian Shatto, x224 to schedule an inspection when utility work is completed.

Kyle E. Torster, P.E.
Director of Public Works