



- PERMANENT BRICK, CONCRETE OR APPROVED PRECAST PIPE SUPPORTS (NOT SHOWN) TO BE PLACED UNDER ALL FLANGED FITTINGS AND AS DIRECTED BY THE CITY OR COUNTY.
- ALL FITTINGS AND PIPE WITHIN VAULT SHALL BE BRASS WITH APPROPRIATE ADAPTORS
- 3. SET VAULT ON A LEVELING COURSE OF AASHTO M43 SIZE 57 AGGREGATE
- 4. PROVIDE POSITIVE DRAJNAGE AWAY FROM VAULT.
- SIMILAR DESIGN OF PIPING AND EQUIPMENT FOR COMMERCIAL INTERIOR BUILDING INSTALLATIONS.
- TYPE 'K' COPPER TUBING SHALL BE CONTINUOUS BETWEEN MAIN, VALVEAND VAULT, ETC. USING SPECIFICALLY ORDERED MAXIMUM AVAILABLE LENGTHS.
- SUMP SHALL HAVE AN 8" MINIMUM DIAMETER AND A 4" MINIMUM DEPTH.
- 8. SOLDERED COPPER JOINTS ARE PROHIBITED.
- PRIOR TO ORDERING THE METER, VAULT AND BACKFLOW PREVENTER, THE CONTRACTOR SHALL MEET WITH CITY AND COUNTY PERSONNEL TO DISCUSS INSTALLATION REQUIREMENTS.
- THE EXTERIOR OF THE CONCRETE VAULT SHALL HAVE A FACTORY APPLIED BITUMINOUS COATING.



CITY OF ABERDEEN
DEPARTMENT OF PUBLIC WORKS

He Toutes

STANDARD WATER DETAILS

OUTSIDE SETTING
1 1/2" AND 2" METERED SERVICE

CITY OF ABERDEEN ADDENDUM TO HARFORD COUNTY STANDARD DETAILS

PLATE W-23